

Commissioning Aqualift F Compact

Article information

Item no.: 80202

GTIN:

Price group: 00

Description

Commissioning of the lifting station Aqualift F Compact, exposed installation / floor slab installation

Scope of services:

- Inspection according to the inspection card
- Briefing on the functionality of the system
- Explanation of the monthly inspection by the owner-operator
- Information on the maintenance obligation for the owner-operator
- Concluding an optional maintenance contract with the client (regular maintenance is a prerequisite for the warranty and insurance cover)
- Installing the control unit / warning device on the wall
- Installing the electrical components on the system
- Routing the electrical cables and air hose through the cable duct to the control unit and connecting them (max. cable length $5\,\mathrm{m}$)
- System is handed over in a safe operational state

Requirements on site:

- Contact person must also be on site
- Access to the system and control unit
- Hose connection must be present
- Wastewater discharge is connected
- Electrical components and small parts must be available in full on site
- Pump tank must be clean
- Inlet pipes must be flushed
- Ventilation pipe of the lifting station is connected
- Pressure pipe is fully installed

Note:

- The flat commissioning rate includes a maximum of 2 installation hours on site.
- Any additional incidental expenses are charged based on the expenses incurred
- The stated price is a net price and therefore not eligible for a discount.



Lifting stations must be regularly serviced by a specialist company in accordance with DIN EN 12056-4.

The following intervals must not be exceeded:

- 3 months for systems in commercial use
- 6 months for systems in multi-family homes
- 1 year for systems in single-family homes

From the commissioning to the execution of the service, a processing time of 10 working days should be expected.