

Commissioning EasyClean ground Multi

Article information

Item no.: 917415/M

GTIN:

Price group: 00

Description

Commissioning the EasyClean ground Multi

Scope of services

- Carrying out a check in accordance with the inspection card (Aquapump XL)
- Proper instruction on the design, function and operation of the systems
- Explanation of the control measures to be carried out monthly by the owner-operator
- Setting of all system-specific parameters in accordance with local conditions (e.g. Sonic Control for grease separators)
- Reference to the owner-operator's statutory maintenance obligations
- Option to conclude a maintenance contract with the client (regular maintenance is a prerequisite for the warranty and insurance cover)
- Handover of the systems in a safe and functional condition

Requirements on site

- A contact person must be on site throughout the entire commissioning process.
- Free access to the systems and the respective control units
- Switching/warning and control devices are installed correctly
- Electrical components, pumps and level sensors are installed and correctly connected.
- Aquapump XL pump is hooked up
- Grease separator (version without technology) is completely filled with water
- Hose connection is available in the immediate vicinity of the systems
- Wastewater discharge is connected
- Inlet, drain and vent pipes are installed
- Pressure pipe (Aquapump XL) is fully installed
- Disposal pipe and water connection to the filling unit (grease separator) are available
- Pump chamber is in a clean condition
- Inlet pipes are flushed
- All electrical components and small parts are available on site
- For systems with remote control: the remote control is installed and the control cable is laid and connected on site
- Installation and operating instructions must be available on site.
- For versions with a pump (grease separator): instruction is provided during the initial disposal process; a waste disposal company must be provided.

Chamber systems

The following requirements apply for service or commissioning work in chamber installations in accordance with BGV C5 §34 and BGR 236:

- Clearance measurement of sewer gases
- Use of anti-fall protection equipment
- Provision of an additional safety attendant
- The safety attendant must be provided by the customer and must be present for the entire duration of the commissioning

Maintenance obligations for grease separators

- Annual maintenance required by a competent expert / inspector
- Lifting stations (Aquapump XL) in accordance with DIN EN 12056 4

Commercial business every 3 months

Apartment buildings every 6 months

Detached houses annually

Notes

- Fixed commissioning rate for grease separators: max. 1.5 hours of a technician being on-site
- Aquapump XL commissioning rate: max. 2 hours of a technician being on-site
- Any additional costs incurred will be charged according to actual expenditure.
- Prices quoted are net prices and are not subject to a discount.
- For grease separator versions PV, D+S and M, instruction is provided as part of the initial disposal process.
- Processing time from order placement to execution: approx. 10–15 working days
- Prices include travel to and from the site.